



CENTRAL RAILWAY
Office of the Financial Advisor & Chief Accounts Officer (Const),
6th Floor, New Administrative Building, D N Road,
CSM Terminus, Mumbai – 400 001.
☎ - 54459

No. CHQ-AC/EST/ROB-LC-73-/KYN-IGP/2510

Date: 23/12/2025

CE(C)RSP
CSMT.

Sub.-:Vetting of Detailed Civil Estimate of LC-73 at Km106/13-14 on KYN-IGP section of BB Division

Civil Sub Estimate for the subject project received CE(C) RSP's letter no. RSP/DE/LC-73, Km 106/13-14 on KYN-IGP section of BB division dated 05/12/2025 & 17/12/2025 has been scrutinized and following observations are made: -

1. The cost of initially proposed Civil Estimate was ₹ 32,24,14,230.11.
2. During scrutiny, it was observed that there was a calculation mistake in schedule-A-I. The same was asked to be rectified. Hence, due to correction the amount of Schedule-A-1 has been modified from Rs. 2,71,33,833.91 to Rs. 2,72,16,493.90. Simultaneously the cost of civil estimate has been revised to ₹32,25,13,463.
3. Schedule A-I, A-II, D & E consists of USSOR-2021 items which have been duly checked and found correct. The same are escalated using latest LAR's which are found correct.
4. Schedule B consists of DSR 2023. As per Dy. CE Works's letter no. W.187.R.USSOR/BCI dated 15/09/2025, it has been stated the escalation @ -24.59% should be considered on DSR 2021 items. Hence, the same has been done. The same has been checked and found correct.
5. In case of Schedule-C of NS items item no- 1 & 2, connected WPI has been rectified and in case of Sr No-9 connected rate reference has been given and found correct. In case of Sr. No 10 & 12 it is clarified that items are different. In view of above Schedule-C amount has been rectified from Rs.7,30,66,421.53 to Rs.7,30,76,546.43.
6. Schedule-F consists of Land Portion. Value of assets Rs.50,00,000/- has been removed. Land cost has been revised from Rs.3,01,12,672.18 to Rs.2,51,12,672.18. The same has been checked and found correct.
7. Utility shifting works of Approach portions (Overhead wire)Rs.50,00,000/- has been removed from estimate
8. As per letter No.2024/CE-IV/Utility-shifting/ROB-RUB(E.O. No-3459904) dtd. 14.05.2025,Part estimates for utility shifting will require personal approval of DRM with Finance concurrence.
9. Total Civil Engg. Cost of the project is given in the table below: -

Department	Cost
Civil Engg.	Rs 32,25,13,463.00
(+) Cost of Land	Rs 2,51,12,672.18
TOTAL	Rs. 34,76,26,135.18

10.The Variation Statement of Abstract Estimate with respect to Detailed Estimate is as per the table indicated below.

Dept	Abstract Estimate	Detailed Estimate	Price Escalation	Other than Price Escalation
------	-------------------	-------------------	------------------	-----------------------------

Civil	33.608	32.251	0.000	-4.04%%
Civil(Land)	Nil	2.512	0.000	100.00%
Total	33.608	34.763	0.000	3.43%%

In view of the above observations, the Civil Sub Estimate of LC-73 at Km 106/13-14 on KYN-IGP section of BB division is vetted for the cost of Rs. 34.76 Crore.

Subject to: -

1. Updating Narrative Report for the modified cost may be placed on record.
2. It may be ensured that there is no deviation in the scope of the work.
3. Quantity proposed to be certified as reasonable & justified as per actual requirement/approved drawing by Competent authority.
4. A copy of approval of new GAD may be placed on record.
5. The undertaking that items & services if available in GeM will be procured through GeM only needs to be placed on record by all the departments as per Railway Board letter no 2020/RS(M)GeM/Action Plan dated 3.9.2020.

This has the approval of FA&CAO(C)

DA: Estimate file.


 (Prateek Singh Meena)
 Dy. FA&CAO(C)-I