TO MULTAI SIDE ROAD
167.251 mtr.
LENGTH OF RCC RET. WALL
A1
P1
P2
P3
P4
P5
P6
P7
P8
P9
RP1
RP2
RP3
P10
P11
P12
P13
P14
A2
TO BORDEHI SIDE ROAD
132.553 mtr.
LENGTH OF RCC RET. WALL
℄ OF EXP. GAP 40MM
24600 EXP. / EXP.
24000 BRG/ BRG.
15500 EXP. / EXP.
19784 EXP. / EXP.
18704 BRG/ BRG.
19080 EXP. / EXP.
18000 BRG/ BRG.
56080 EXP. / EXP.
54000 BRG/ BRG.
12776 EXP. / EXP.
40 mm EXP. GAP
60 mm EXP. GAP
80 mm EXP. GAP
℄ OF BEARING
65 THK WEARING COAT
GRADIENT 1 IN 32.2
GRADIENT 1 IN 28.5
GRADIENT 1 IN 30
GRADIENT 1 IN 41.6
SOLID SLAB
4Nos. GIRDER AS / MORTH
MORTH RCC T-BEAM REFER DRG.NO=SD/211
5Nos. GIRDER AS PER DESIGN
COMPOSITE GIRDER AS PER DESIGN
OPEN WEB GIRDER AS PER DESIGN
225 THICK SLAB
FINISHED ROAD LEVEL 766.402
765.112 SOFFIT LEVEL
6250 MINIMUM (VERTICAL CLEARANCE)
PROTECTIVE SCREEN
POT/PTFE BEARING (TYP.)
INSPECTION PLATFORM
R.C.C ABUTMENT
R.C.C PIER
300 THK. DIRT WALL
FOUNDING LEVEL 754.009
FOUNDING LEVEL 753.846
FOUNDING LEVEL 753.917
FOUNDING LEVEL 754.296
FOUNDING LEVEL 754.213
FOUNDING LEVEL 754.429
FOUNDING LEVEL 754.718
FOUNDING LEVEL 754.747
FOUNDING LEVEL 754.819
FOUNDING LEVEL 754.908
FOUNDING LEVEL 755.081
FOUNDING LEVEL 755.100
FOUNDING LEVEL 755.205
FOUNDING LEVEL 755.209
FOUNDING LEVEL 755.196
FOUNDING LEVEL 755.159
FOUNDING LEVEL 755.098
FOUNDING LEVEL 755.084
FOUNDING LEVEL 755.203
150mm THIK PCC M15
6500
3500
2000
EXISTING C.RLY BOUNDARY 5046 (SK) 4767 (SQ)
EXISTING TRACK UP MAIN LINE 5020 (SK) 4740 (SQ)
EXISTING TRACK DN MAIN LINE 6458 (SK) 6100 (SQ)
PROPOSED LOOP DN 7863 (SK) 7430 (SQ)
PROPOSED 3rd LINE 6460 (SK) 6100 (SQ)
PROPOSED LOOP 6503 (SK) 6100 (SQ)
FUTURE TRACK 4TH LINE 6595 (SK) 6100 (SQ)
SHUNTING NECK LINE
RAIL TOP LVL
7841 (SK) 7400 (SQ)
7161 (SK) 6478 (SQ)

SECTIONAL ELEVATION A-A

SCALE 1:150

	A1	P1	P2	P3	P4	P5	P6	P7	P8	P9	RP1	RP2		RP3	P10	P11	P12	P13	P14	A2
Proposed Road Level	761.123	761.875	762.627	763.101	763.575	764.048	764.522	764.996	765.470	765.918	766.284	766.402	766.402	766.402	766.255	766.046	765.689	765.319	764.949	764.579
Existing Ground Level	757.509	757.346	757.417	757.796	757.713	757.929	758.218	758.247	758.319	758.408	758.581	758.600	758.662	758.705	758.709	758.696	758.659	758.598	758.584	758.703
Chainage	167.000	191.600	216.200	231.700	247.200	262.700	278.200	293.700	309.200	324.700	344.484	363.564	391.604	419.644	432.420	445.196	460.696	476.196	491.696	507.196


TO MULTAI SIDE ROAD
3000 SERVICE ROAD
12000 OVERALL DECK WIDTH
9000 CARRIAGEWAY
1000
1300
200
DRAIN
RCC RAILING
FOOTPATH
24600 (c/c EXPANSION GAP)
15500 (c/c EXPANSION GAP)
19784 (c/c EXPANSION GAP)
19080 (c/c EXPANSION GAP)
56080 (c/c EXPANSION GAP)
12776 (c/c EXPANSION GAP)
R50000
R100000
BH-1
BH-2
BH-3
BH-4
BH-5
BH-6
BH-7
BH-8
C/L OF SYMMETRY
TO MULTAI RAIL STATION (897.74 KMS.) >>>
<<< TO HATANAPUR RAIL STATION (907 KMS.)
EXISTING C.RLY BOUNDARY
EXISTING TRACK UP MAIN LINE
EXISTING TRACK DN MAIN LINE
PROPOSED LOOP DN LINE
PROPOSED 3rd LINE
PROPOSED LOOP UP LINE
FUTURE TRACK 4TH LINE
SHUNTING NECK LINE
TO BORDEHI SIDE ROAD
UP
HALF TOP PLAN
HALF BOTTOM PLAN
PLAN
SCALE 1:150
℄ PROPOSED ROAD
12000 OVERALL DECK WIDTH
1500
9000 CARRIAGEWAY
450
ROAD LEVEL
DRAINAGE SPOUT
65 THK. WEARING COAT
CONSTRUCTION JOINT
HAUNCH 150X75
PIER CAP TOP LVL.
℄ OF BRG.
EXISTING G.L
EXISTING G.L 757.992
FOUNDING LEVEL 754.492
9000
12900
FOO TPATH
CRASH BARRIER
RCC RAILING
2.5% SLOPE
END CROSS GIRDER
INSPECTION PLATFORM
11500
6500
EXISTING G.L 758.579
FOUNDING LEVEL 755.079
C/L OF PROPOSED ROAD
12900 OVERALL DECK WIDTH
RAILING
FOOTPATH
65 MM W.C
SLAB 225 mm THK.
ROAD LEVEL 766.402
TOP PLATE
PIER CAP TOP LVL. 764.612
INSPECTION LADDER
PIER CAP BOTT. LVL. 763.112
BOTTOM FLANGE PLATE
BOTTOM PLATE
13563
4250
15000
1100
EXISTING G.L 758.600
FOUNDING LEVEL 755.100
10000
SPAN-24M MORTH
℄ OF EXP. GAP 40MM
℄ OF BEARING
40 mm EXP. GAP
65 THK WEARING COAT
DIRT WALL
PLATFORM INSPECTION
R.C.C ABUTMENT
SPAN-15.5M SOLID SLAB
RCC PIER
SPAN-19.784M COMPOSITE GIRDER
SPAN-19.080M COMPOSITE GIRDER
℄ OF EXP. GAP 80MM
80 mm EXP. GAP
225 mm THK. SLAB
COMPOSITE GIRDER AS PER DESIGN
POT/PTFE BEARING (TYP.)
SPAN-56.080M OPEN WEB GIRDER
250 mm THK. SLAB
PROTECTIVE SCREEN
SERVICE ROAD
100MM DIA 5000 C/C
200 600 200
1200
RCC RAILING
DRAINAGE SPOUT
3000 SERVICE ROAD 2.5% SLOPE
RCC RET WALL
DRAIN
SERVICE ROAD TRAFFIC DIVERSION ROAD AT THE TIME OF CONSTRUCTION
G.L. 757.929
G.L. 758.247
G.L. 758.408
G.L. 758.600
G.L. 758.705
G.L. 758.696
G.L. 758.598
G.L. 758.703
Murum
Brownish Fractured Weathered Rock
Greyish Basalt Rock

SECTION C-C
(SCALE 1:75)
MORTH RCC T-BEAM REFER DRG.NO=SD/211

SECTION D-D
(SCALE 1:75)
COMPOSITE GIRDER AS PER DESIGN

SECTION E-E
(SCALE 1:75)
AS PER DESIGN

DETAIL-'1'
(SCALE 1:50)

DETAIL-'2'
(SCALE 1:50)

DETAIL-'3'
(SCALE 1:50)

DETAIL-'4'
(SCALE 1:50)

DETAILS OF BORE HOLE NO-8

DETAILS OF BORE HOLE NO-7

DETAILS OF BORE HOLE NO-6

DETAILS OF BORE HOLE NO-5

DETAILS OF BORE HOLE NO-4

DETAILS OF BORE HOLE NO-3

DETAILS OF BORE HOLE NO-2

DETAILS OF BORE HOLE NO-1

TYPICAL SECTION OF THRO RE wall
(SCALE 1:20)

TYPICAL SECTION B-B THRO RE WALL
(SCALE 1:50)


TOTAL LENGTH 640.000 MTR.
TO MULTAI SIDE ROAD
167.251 mtr.
LENGTH OF RCC RET. WALL
TO BORDEHI SIDE ROAD
132.553 mtr.
LENGTH OF RCC RET. WALL
A1 P1 P2 P3 P4 P5 P6 P7 P8 P9 RP1 RP2 RP3 P10 P11 P12 P13 P14 A2
24600 24600 15500 15500 15500 15500 15500 15500 15500 19784 19080 56080 12776 12776 15500 15500 15500 15500
SLOP 1:32.2
SLOP 1:41.6
C/L OF PROPOSED TRACK LOOP DN LINE
C/L OF PROPOSED TRACK 3rd LINE
C/L OF PROPOSED TRACK LOOP UP LINE
C/L OF FUTURE TRACK 4TH LINE
C/L OF SHUNTING NECK LINE
C/L OF EXISTING TRACK DN MAIN LINE
C/L OF EXISTING TRACK UP MAIN LINE
EXISTING C.RLY BOUNDARY
LEVEL DATUM = 756.000
HORIZONTAL ALIGNMENT
L:236.64
Ls: 30.000 LT: 20.095 ST: 10.087 K: 14.955
PI STA: 0+305.12 D: 75°09'52.83" R: 50.00 L: 65.59
L:50.66
Ls: 20.000 LT: 13.340 ST: 6.673 K: 9.997
PI STA: 0+484.52 D: 54°36'30.18" R: 100.00 L: 95.31
L:36.41
Ls: 20.000 LT: 13.377 ST: 6.707 K: 9.979
PI STA: 0+632.88 D: 70°29'01.97" R: 40.00 L: 49.21
VERTICAL ALIGNMENT
G: 0.5% L: 18.700
R: 1934.9 K: 19.3 L: 50.000
G: 3.1% L: 254.078
R: 1561.7 K: 15.6 L: 47.732
G: 0.0% L: 46.140
R: 1772.3 K: 17.7 L: 42.301
G: -2.4% L: 142.667
R: 2129.4 K: 21.3 L: 50.000
EXTRA WIDENING RHS LHS
0.6 0.6 0.45 0.45 0.75 0.75
SUPER ELEVATION RHS LHS
e=2.5% e=2.5% e=7.0% e=7.0% e=2.5% e=2.5% e=7.0%

CHAINAGE	PROPOSED ROAD LEVEL	EXISTING GROUND LEVEL
-20.000		756.600
-10.000		
0.000	756.968	756.623
10.000		
20.000	757.079	756.563
30.000		
40.000	757.359	756.643
50.000		
60.000	757.847	756.809
70.000		
80.000	758.457	757.572
90.000		
100.000	759.068	757.956
110.000		
120.000	759.679	757.823
130.000		
140.000	760.291	757.690
150.000		
160.000	760.902	757.557
170.000		
180.000	761.513	757.425
190.000		
200.000	762.125	757.292
210.000		
220.000	762.736	757.523
230.000		
240.000	763.347	757.635
250.000		
260.000	763.959	757.879
270.000		
280.000	764.570	758.249
290.000		
300.000	765.181	758.218
310.000		
320.000	765.788	758.373
330.000		
340.000	766.221	758.579
350.000		
360.000	766.397	758.596
370.000		
380.000	766.402	758.611
390.000		
400.000	766.402	758.586
410.000		
420.000	766.374	758.705
430.000		
440.000	766.147	758.711
450.000		
460.000	765.712	758.660
470.000		
480.000	765.235	758.570
490.000		
500.000	764.757	758.639
510.000		
520.000	764.280	758.866
530.000		
540.000	763.803	759.292
550.000		
560.000	763.325	759.813
570.000		
580.000	762.848	760.333
590.000		
600.000	762.377	760.859
610.000		
620.000	762.041	761.288
630.000		
640.000	761.893	761.591
650.000		
660.000	761.880	761.923
670.000		
680.000	761.872	761.915

LONGITUDIONAL ELEVATION
NOT TO SCALE

LEGEND:-

▨	- RE WALL
▬ ╎╎╎ ▬	- RAILWAY BOUNDARY
	- EXISTING WORKS SHOWING IN BLACK
	- PROPOSED WORK SHOWING IN RED
	- FUTURE LINE SHOWING IN GREEN


N
TO BORDEHI SIDE ROAD
TO MULTAI SIDE ROAD
PROPOSED LAND AREA REQUIRED 7221.9578sqm2
PROPOSED LAND AREA REQUIRED 356.8116sqm2
PROPOSED LAND AREA REQUIRED 1600.4417sqm2
PROPOSED RAILWAY BOUNDARY DWG. NO: G.M (W) BB/P-16136
RLY. BOUNDARY
RLY. QUARTERS
QUARTERS
WELL
HOUSE
SHOP
TBM 1
TBM 2
TBM 3
TBM 6
TBM 7
PROPOSED LHS AT LC.265 SPL CLASS (M) (KM.897/42-898/2)
PROPOSED ROB AT LC.265 SPL CLASS (M) (KM.898/2-898/4)
<<< TO MULTAI RAIL STATION (897.74 KMS.)
TO HATANAPUR >>> RAIL. STATION (907.00 KMS.)
MAIN POWER LINE
FENCING
TRD SECTION
Curve No:-1
Curve No:-2
Curve No:-3
Curve No:-4

KEY PLAN FOR LC NO. 265

TABLE FOR TBM COORDINATE

TBM NUMBER	COORDINATE		
	X	Y	Z
TBM-1	217042.2315	2411215.1957	0.5830
TBM-2	217284.2747	2411177.4386	0.5830
TBM-3	217068.8991	2411219.3159	0.5830
TBM-4	216951.8424	2411040.3166	0.5830
TBM-5	216955.6788	2411045.1713	0.5830
TBM-6	217303.4842	2411258.4302	0.5830
TBM-7	217329.0107	2411291.4391	0.5830

ABBREVIATIONS:

F.R.L.	FORMATION LEVELS
GL	GROUND LEVEL
CL	CENTRE LINE
CH	CHAINAGE
TYP.	TYPICAL
THK.	THICK
LVL.	LEVEL

BORE HOLE NUMBER & GPS LOCATION

BORE HOLE NUMBER	GPS LOCATION	
	X	Y
BH1	217283.5427	2411373.8259
BH2	217309.8826	2411358.0484
BH3	217330.3550	2411334.7701
BH4	217341.1677	2411311.6755
BH5	217350.3208	2411256.3205
BH6	217354.9634	2411217.7381
BH7	217348.1234	2411187.5577
BH8	217324.9597	2411166.9556

1- GENERAL NOTES:-

DESIGN ARE CARRIED OUT FOR MODERATE EXPOSURE

(1) ALL DIMENSIONS ARE IN MILLIMETERS AND LEVELS ARE IN METERS UNLESS OTHERWISE MENTIONED.
(2) NO DIMENSIONS SHALL BE SCALED FROM THE DRAWING. ONLY WRITTEN DIMENSIONS SHALL BE FOLLOWED.
(3) THE STRUCTURAL DETAILS AND DIMENSION SHOWN IN THIS DRAWING ARE TENTATIVE AND ARE SUBJECT TO CHANGE AS PER DESIGN AND DRAWING APPROVED BY THE RAILWAY.
(4) CRS SANCTION SHOULD BE OBTAINED BEFORE STARTING THE WORK IN RAILWAY SPAN.
(5) DEPTH OF FOUNDATION IS TENTATIVE AND MAY BE ALTERED BY ENGINEER-IN-CHARGE OF RAILWAY TO SUIT THE SOIL STRATA MET AT SITE.
(6) THE PILE LOAD TEST SHALL BE CARRIED OUT BEFORE CASTING OF PILE AS PER RELEVANT IRC/RAILWAY CODE.
(7) GUARD RAIL SHALL BE PROVIDED IN THE TRACK ADJACENT TO PIERS AND ABUTMENTS AS PER STANDARD DRAWING.

2- TECHNICAL NOTES:-

(8) POT/PTFE BEARING SHALL BE PROVIDED UNDER COMPOSITE SUPERSTRUCTURE.
(9) IN CASE BLASTING TO BE CARRIED OUT IN THE VICINITY OF RAILWAY LINE NECESSARY PRECAUTIONS AND BLOCK SHALL BE FOLLOWED AS PER PARA 1006 OF IR WORKS MANUAL.
(10) FOR FABRICATION OF STEEL GIRDERS, RDSO GUIDE LINES BS: 110 REVISED 112 AND SPECIFICATIONS OF B-1 SHALL BE FOLLOWED.
(11) CONTROLLED CEMENT CONCRETE MIX TO PROVIDED AND SHOULD NOT BE LESSER THAN PROVISIONS IN RAILWAY'S CONCRETE BRIDGE CODE.
(12) DURING THE CONSTRUCTION OF ROB THE TRACK WILL BE SUITABLY PROTECTED SUITABLY SPEED RESTRICTION SHALL BE IMPOSED IF REQUIRED.
(13) THE SAFE BEARING CAPACITY OF PILE FOUNDATION SHALL BE AS PER GEO TECHNICAL INVESTIGATION REPORT.
(14) STRIP SEAL TYPE EXPANSION JOINT SHALL BE PROVIDED AT EACH JOINT LOCATION.
(15) MOU TO BE DRAWN WITH TRAFFIC DEPT FOR BLOCK AND CAUTIONS BEFORE STARTING THE WORK
(16) IT SHALL BE ENSURED THAT THE REPRESENTATIVE FROM SIGNAL & TELECOM DEPT ARE MADE AVAILABLE BEFORE THE WORK IS COMMENCED IN VICINITY OF SIGNALING & OR TELECOM CABLE
(17) ROTARY IF REQUIRED AT JUNCTION SHALL BE PROVIDED AS PER SITE CONDITION.
(18) BEFORE OPENING OF ROB FOR ROAD TRAFFIC APPROVAL OF RAILWAY ENGINEER IN CHARGE TO BE OBTAINED.
(19) MAINTAINANCE IN RAILWAY PORTION OF ROB IS DONE BY RAILWAY AND OUTSIDE RAILWAYS BOUNDARY WILL BE DONE BY STATE GOVERNMENT.
(20) DRAINAGE SPOUT SHALL BE PROVIDED AS PER SPECIFICATION WATER MUST NOT FALL ON RLY. TRACKS. THE WATER FROM DRAINAGE POTS SHALL BE COLLECTED AND DISCHARGED IN DRAIN, OUTSIDE RAILWAY TRACKS.
(21) A SEPARATE GAD FOR VEHICULAR UNDERPASS WILL BE SUBMITTED FOR RAILWAY APPROVAL.
(22) THE INTERFACE BETWEEN THE PLIES WHICH ARE CONNECTED TOGETHER BY THE HSFG BOLTS SHALL BE "ALUMINIUM METALLISED WITHOUT ANY OVER COATING". THE ALUMINIUM METALLIZING SHALL BE AS PER PARA 39.2.1 OF IRS B1.
(23) THE SEPARATE LAUNCHING TAD SHALL BE PREPARED AND SUBMITTED FOR HQ APPROVAL.

3- CLEAR COVER:-

(24) DIRT WALL SHALL BE 50 mm. (25) EARTH SIDE SHALL BE 75 mm. (26) NON EARTH SIDE SHALL BE 50mm.

4- GRADE OF CONCRETE:-

(27) PCC	:M15	CRASH BARRIER	:M40	FOUNDATION	:M35	RCC BOX	:M45
SUBSTRUCTURE	:M35	PIER CAP / ABT.CAP	:M35	DECK SLAB / PEDASTAL	:M40	RETAINING WALL	:M35

5- REFERENCES:-

(28) THE ACTIVITY OF CONSTRUCTION METHODOLOGY, SAFELY PRECAUTIONS AND MEASURES TO BE OBSERVED AND CONSTRUCTION OF ROB SHOULD BE IN ACCORDANCE OF BOARD'S LETTER NO. 97/CE01/BRO/158/9(POLCY) PT.LL DATED 16.7.2009
(29) THE DETAILS OF CRASH BARRIER SHALL BE AS PER RDSO DWG. NO. RDSO/B-11776/4
(30) FABRICATION OF GIRDERS WILL BE DONE IN RDSO APPROVED WORKSHOP. LAUNCHING OF GIRDERS SHALL BE SUPERVISED BY REPUTED THIRD PARTY CONSULTANT AS IN ACCORDANCE WITH RB'S LETTER DATED 26.05.2017.
(31) SAFETY RELIABILITY AND LONG LIFE TERM DURABILITY OF THE OVERHEAD STRUCTURE SHALL BE ENSURED DURING THE DESIGN AND EXECUTION STAGES AS PER LETTER NO.W.641.BR.POLICY DATED. 10.10.2018.
(32) FIXING OF AGENCY FOR FABRICATION OF GIRDER SHALL BE GOVERNED BY RAILWAY BOARDS INSTRUCTION NO. 23/2019 ISSUED VIDE LETTER NO 2016/54/CE III/BR/RDSO MISC. DATED 15/07/2019
(33) COMPLETION DRAWING OF ROB SHALL BE SUBMITTED TO THE RAIKLWAY FOR APPROVEL.
(34) PROTECTION ARRANGEMENT OF WORKSITE SHALL BE DONE AS PER I RPWM AND RAILWAY BOARD'S INSTRUCTIONS.
(35) AT APPROACH A1 SIDE HEIGHT DIFFERENCE BETWEEN HIGH TENSION WIRE TO EXISTING ROAD LEVEL IS 16.00 METER & AT APPROACH A2 SIDE HEIGHT DIFFERENCE BETWEEN HIGH TENSION WIRE TO EXISTING ROAD LEVEL IS 21.00 METER.
(36) A SEPARATE GAD FOR STAIRCASE WILL BE SUBMITTED FOR RAILWAY APPROVAL.
(37) BEYOND RAILWAY BOUNDARY LAND TO BE ACQUIRED BY CONCERNED STATE AUTHORITY.
(38) SCREEN PROTECTION FOR RAILWAY PORTION AS PER (RDSO DRAWING NO. ETI/C/0068.)

6- DRAWING REFERENCES :-

(39) DRAWING AND DESIGN OF APPROACH SLAB SHALL BE AS PER CLAUSE 214.2 OF IRC-6-2017
(40) REFERENCE DRG FOR MORTH DRG NO:-24.0m DRG NO. SD / 200 TO SD / 217 SH-2
(41) REFERENCE DRG FOR COMPOSITE GIRDER 18.0 M REFFER AS PER DESIGN
(42) REFERENCE DRG FOR OPEN WEB GIRDER 54.0 M SPAN AS PER DESIGN

7- SPECIFICATIONS:-

(43) DESIGN IS BASED ON FOLLOWING CODES :-
- (a) IRC-5 - SECTION-I GENERAL FEATURE OF DESIGN
- (b) IRC-6 - SECTION-II LOADS AND STRESSES
- (c) IRC-21 - SECTION-III CEMENT CONCRETE
- (d) IRC-78 - FOUNDATION AND SUB STRUCTURE
- (e) IRC-24 - DESIGN OF PLATE GIRDER
- (f) IRC-22 - COMPOSITE CONSTRUCTION
- (g) IRC-83 - (PART III) POT PTFE BEARING
- (h) IRC-83 - (PART II) ELESTOMERIC BEARING

9- LOADING:-

a) IRC CLASS-A LOADS OR 1 LANE OF IRC CLASS 70R LOAD AS PER IRC-6 WHICHEVER PRODUCES WROST EFFECT SHALL BE PROVIDED.
c) THE ROB SHALL BE DESIGNED CONSIDERING SPECIAL VECHICLE LOAD AS PER IRC-6 (LATEST).
b) THE CARRIAGE WAY WIDTH SHALL BE CONSIDERED INCLUDING FOOTPATH & INTERNAL CRASH BARRIER IN THE DESIGN.

10- SESMIC ZONE:-

(45) SEISMIC ZONE II SHALL BE CONSIDERED IN THE DESIGN

11- SCOPE OF WORK:-

RAILWAY: RP1 TO RP3
PWD/ROAD AUTHORITY : A1 TO RP1 AND RP3 TO A2 INCLUDING BOTH SIDE APPROCHES

NOTE: COST OF ADDITIONAL WIDTH OF CARRIAGEWAY OF 1.5 M (9.0-7.5M)WILL BE FULLY BORNE BY ROAD AUTHORITY/PWD BHOPAL

REVISION :R1

DESCRIPTION	AS PER OLD GAD	REVSION
SPAN ARRAGEMNET RAILWAY PRTION	1/18.0 + 1/49.7M +1/18M COMPOSITE GIRDER	1/18.0 M C.G + 1/54m OPEN WEB GIRDER
SPAN ARRANGEMENT APPROACHES(PWD) SPAN		
MULTAI SIDE	9/24.0 RCC T BEAM GIRDER 119.054MRW	2/24.0 RCC GIRDER+7/15.5M SOLID SLAB +1/18.704M COMPOSITE GIRDER RW-167.251M
BORDAI SIDE	5/24.0 RCC T BEAM GIRDER+77.008M RW	2/12.776+4/15.5M SOLID SLAB +132.553M RW
CARRIGWAY SIDE	7.5M	9.0(AS PER PWD DRAWING FOR APPROACHES)
ROAD LEVEL AT ROB TOP	768.393M	766.402M

LKT OFFICIALS

DESIGNATION		SIGNATURE
PREPARED BY	SR. DAFTSMAN	(RAKESH)
DESIGNED BY	SR. STRUCTURAL ENGINEER	(CHANAN PREET)
CHECKED BY	SR. STRUCTURAL ENGINEER	(GAURAV)
APPROVED BY	MANAGING DIRECTOR	(LOKESH TYAGI)

PWD

DESIGNATION	SIGNATURE
CE	SIGNATURE OF PWD DEPARTMENT AS UNDER PROCESS
SE	
EE	
SDO	
Sub Engineer	

NO.	DATE	REVISION	REMARK

CLIENT
CENTRAL RAILWAY
(HQ BRIDGE - SPL)

PROJECT CONSULTANT :-
LKT Engineering Consultants Ltd.
Flat No – 75/288 SFS G-8-A Rajouri Appartment,
Rajouri Garden New Delhi-110064 Phone :+011-45565818
info@lktengineering.com

NAGPUR DIVISION

L - XING NO.265 ON CRLY KM. NO. 898/2-898/4
BETWEEN AMLA-NAGPUR SECTION

TITLE :-
GENERAL ARRANGEMENT DRAWING OF PROPOSED 2 LANE ROB ROAD OVER BRIDGE IN LIEU OF LEVEL CROSSING GATE NO. 265 SPL CLASS (M) ON CRLY KM 898/2-898/4 BETWEEN MULTAI RAILWAY STAION (897.74 KM) -HATNAPUR RAILWAY STAION (907.00 km) SPAN (2X24.0 MORTH GIRDER +7X15.50 SOLID SLAB+1X19.784 COMPOSITE GIRDER+1X18.0 COMPOSITE GIRDER +1X54.0 OWG+2X12.776 SOLID SLAB+4X15.500 SOLID SLAB)

PINK BOOK ITEM NO. – 212 OF 2020-21

50-50% COST SHARING BASIS

SCALE: – AS SHOWN	DRG. NO. Dy.CE(C) NGP R-8820
	DRG. NO. GM(E) MB-99697
	DRG. NO. GM(W) BB/P-
LKT DRAWING NO.	LKT / CR / ND / LC-265 / GAD-1