

CENTRAL RAILWAY



HEADQUARTERS OFFICE,
ENGINEERING BRANCH,
MUMBAI C.S.T.

No: W/294/Arch Top Box/BSL/III

Date: - 24.07.2018.

Sr.DEN (Co) BSL,

Sub: Proposed rebuilding of existing arch bridge of span 1/2.29m by RCC arch top box with the extension of barrel length.

Ref: Your letter No. BSL/W/127/Br./WP/18-19/10BR Dated 16.07.2018.


With reference to the above subject cited above, the original paper tracing GAD's are duly approved by competent authority and allotted pucca drawing number given below:

Sr. No.	Bridge No.	Divn. Approval DRG. No.	HQ. Approval DRG. No.
1	480/1	DRM(W)BSL/R-8769	GM(W)BB/P-16409

1 nos. Of OPT are sent herewith for your further action please. Scanned copy has been sent to srdencobsl gmail ID.

Completion drawing may be please send to HQ for record after completion of work.

DA:- As above
(1 nos.of OPT)


24.07.18
(A.K.Singh)
DyCE / Br-I

C-287
C-235

2

GOVERNMENT OF INDIA
MINISTRY OF RAILWAYS
(RAILWAY BOARD)

JOINT CIRCULAR

Sub: Mega Traffic-Cum-Power blocks for construction of Grade Separators

Level crossings are potentially unsafe locations, congestion points for road-rail users and operational bottlenecks for Railways, causing loss of line capacity by about 5%. Grade Separator (ROB, RUB, FOB and Subway), in lieu of a level crossing or standalone for track crossing, is a much more beneficial arrangement. It provides seamless movement to road vehicles and trains and vastly improves safety of road-rail users.

It is learnt that Railways are reluctant to plan Subway / RUB, particularly on double line section, from where manned level crossing gates should be eliminated first, for want of certainty and clarity regarding sanction of traffic blocks required for aforesaid purpose. As a result, manning of unmanned level crossings are being done which is not desirable features for the safe & detention free operation of trains as well as road vehicles.

In order to expedite construction of grade separators {on cost sharing, fully at the cost of Railways and deposit terms of sponsoring agencies, like, State Govt., Municipality, BOT, PPP, NHAI, Member of Parliament Local Area Development Scheme (MPLADS), National Rural Employment Guarantee Act (NREGA)}, etc, it has been decided that,

- (i) Railways shall give due importance to grade separator works.
- (ii) Proposals for Traffic Block and speed restriction required for construction of ROB, RUB/Subway, etc, should be sorted out by Zonal Railways, except where the Traffic Block required is of duration more than 08 hours, in which case, Railway Board may be approached.
- (iii) Pr.CE & CAO (C) should devise methodology which aims at minimum traffic blocks and speed restrictions, by use of modern construction machinery and methods, like, heavy duty crane, JCB, pre-cast, pre-fabricated, cut & cover methods for box insertion, etc. Railways must do advance planning for ROB girders launching, insertion of RCC boxes, etc, simultaneously at many sites in Mega Block and its shadow block, to maximize block output.
- (iv) Sanctity of duration of Block should be maintained. Additional equipments like Crane, JCB, Jacks, etc, may be kept at site to take care of failure of any equipment / machinery during block period.
- (v) There should normally be no occasion for Board's intervention in this matter. General Manager shall review all pending cases of blocks & speed restrictions required for construction of ROB, RUB / Subway, etc, at least once a month.


20/01/12
(A.P. Mishra)
Member Engineering


20/01/12
(K. K. Srivastava)
Member Traffic

Letter No. 2011/CE-IV/Traffic Block/ROB-RUB, Railway Board, Dated 20/01/12

Copy to:

- (i) The General Manager, all Zonal Railways
- (ii) The Chief Operating Manager, all Zonal Railways
- (iii) The Principle Chief Engineer, all Zonal Railways *KR*